

Certificate

about the quality of airtightness

Component: Conduit-gang junction box HELIA
Art.-No. 5029

Customer: N.V. PLASTIC COLOR, Puursesteenweg 363, B-2880 Bornem

Test Object:

Housing consisting of plastic-coated chipboards with therein installed
20 Conduit-gang junction boxes HELIA (Art.-No. 5029)
with 40 conduit entries.

Results:

Using the BlowerDoor Micro-Leakage-Meter measurement system and the DG-700
the following values for the airflow and the permeability of building components at
a pressure difference of 10 Pa were achieved:

Airflow at 50 Pascal based on 20 Conduit-gang junction boxes HELIA
with 40 conduit entries:

$$V_{50} = 0,1555 \text{ m}^3/\text{h}$$

Airflow at 10 Pascal relative to the joint length (permeability of building component):

$$\text{leakage rate} = 0,0047 \text{ m}^3/(\text{h} \cdot \text{m})$$

According to DIN 4108-2:2013-02 chapter 7 para. 3, the requirement for component connection joints is $\leq 0.1 \text{ m}^3/\text{mh}$ (daPa^{2/3}).

**The tightness of component connection joints of the
and the Conduit-gang junction box HELIA (Art.-No. 5029)
satisfies the requirements.**



13.03.2018

Dipl.-Ing. Heiko Wandtke

Ingenieurgesellschaft
Bau + Energie + Umwelt GmbH
Zum Energie- und Umweltzentrum 1
31832 Springe-Eldagsen
Telefon 05044 / 975-30
Telefax 05044 / 975-44