

Product datasheet:

Pluggable installation in concrete

· With protective cover.

Article number:	⇒ AT5305
EAN:	8712259599649
Packaging quantity:	25

Dimensions / Form

Product length:	300 mm
Product width:	70 mm
Product depth:	10 mm

Assembly / Installation

Assembly type:	BB (solid construction)
----------------	-------------------------

Safety / Properties

Halogen-free:	Yes
Special application:	on-site mixed concrete



ETIM Product classification:

Cover for box/housing for built-in mounting in the wall/ceiling

Diameter:	
Suitable for box-/housing diameter:	
Length:	300 mm
Suitable for box-/housing length:	300 mm
Width:	70 mm
Suitable for box-/housing width:	70 mm
Depth:	10 mm
Shape:	Rectangular
Type of fastening:	Plug-in cover
Model:	Construction protective cover
With cable outlet:	No
Material:	Plastic
Halogen free:	No
Colour:	Red
RAL-number (similar):	
With screws:	No
Sealable:	No

A large part of the installation can already be prefabricated in the concrete factory with the help of the Sparing boxes.

There is enough space in the floor and wall boxes to store the excess length of the prefab cabling. As soon as the hull has been placed, the installation is plugged together

Product datasheet:

in the floor and wall parts. All flush-mounted and central boxes are also pre-wired, so the connection of the switches and sockets can be performed very quickly.

Non-load-bearing interior walls are powered from wired floor boxes. The flush-mounted boxes in these walls can therefore be connected quickly. Even more time savings are achieved by connecting the switches and sockets in these walls completely pluggable, by using prefabricated mounted switches and sockets in hollow wall boxes.

The floor boxes are also used as temporary storage for the cabling of the outgoing groups from the distribution board. As soon as the distribution board is mounted, it is simply pluggable connected.

- Create installation space in precast concrete.
- Completely pluggable floor and wall boxes.
- Save time with pre-wired flush-mounted and central boxes.
- Prefabricated mounted switching material.